

Project-Specific Special Provisions

Addendum #2

7/18/2024

RIP RAP

The following are modifications to the SCRRA Standard Specifications:

PART 1 - GENERAL

Revise paragraph 4-1 SCOPE

4-1 SCOPE

This work consists of placement of “Loose” (NOT grouted) 1-ton Class IX, Class VIII, and Class I rock riprap. Class IX riprap shall be installed per Caltrans Method A placement per Caltrans Standard Specifications as shown on plans and as directed by the Engineer. Class VIII and Class I riprap shall be installed per Caltrans Method B placement per Caltrans Standard Specifications as shown on plans and as directed by the Engineer.



END OF SECTION 4